Sacramento River Rail Trail Repaving GAOA FY26
Bid Schedule (Base) – Water System

Item	Description of Work	Quantity	Unit	Unit Cost	Cost
1	Mobilization	1	**LS**	$	$
2	Remove and Replace Patching • 100LF x 8ft wide sections, 5 each	4000	**SF**	$	$
3	Surface Preparation	596,687	**SF**	$	$
4	Tack Coat	596,687	**SF**	$	$
5	Conformed Grind - Intersections	7	**EA**	$	$

6	HMA Overlay
	• 3/8-inch NMAS, PG 64-10
	  • Placed in one lift
	  • 0.10 ft compacted thickness
		596,687	**SF**	$	$

7	Shoulder Backing • 0.10 ft compacted Class II base • One foot taper on either side of finished paved surface • Measurement shall be along the trail centerline; quantity includes both sides.	148,157	**LF**	$	$
8	Compaction Testing • 1 per production day or representative production lot	10	**EA**	$	$
				Total	

Bid Schedule (Additive Items) –

Item	Description of Work	Quantity	Unit	Unit Cost	Cost
1	Striping • Apply 4-inch yellow broken centerline • Stripe pattern: 4 ft stripe / 8 ft gap • Striping shall follow alignment of trail centerline	74,078	LF	$	$
				Total	$

GRAND TOTAL (Base items + Additive items)	