Lead Paint Survey

FC444 Aluminum Sulfate Tank Repairs
MCB Camp Lejeune
Project # 25-0087

Report Prepared By:
Christopher B. Walker
The Walker Group Architecture, Inc
June 10th, 2026
WGA Project No. – 2609.SUFL

Project Information

The Walker Group Architecture, Inc. was contracted by NRW Engineering to conduct a lead sampling survey for FC444 Aluminum Sulfate Tank repairs project. The specified structure is slated for demolition and replacement of the tank and associated piping. The survey was conducted to determine if building components were coated with lead-based paint.

Scope of Services

A. The survey was performed on 04/30/2026 by Christopher B. Walker (NC Accredited Lead Inspector #110239 expires August 31st, 2026. Samples were collected from areas defined by the scope of work.

Findings

A. The Walker Group Architecture collected paint chip samples from each surface visibly coated with a different color of paint and delivered them to EMSL Analytical, Inc. (AIHA ELLAP lab code no. 102564) for analysis for lead content by Flame AAS (SW 846 3050B*/7420) in accordance with EPA 3050B/Modified/7000B. OSHA 29 CFR 1926.62 defines any detectable level of lead in paint a concern when renovations/demolitions will impact lead coated surfaces.

B. The detection limit is determined by weight of the sample, which is typically 0.01%. See attached Lab Results for additional information.

Building Description and Findings

FC444 Aluminum Sulfate Tank is a large fiberglass tank supported on a concrete pad. The tank has several appurtenances and sets of piping that route around the tank enclosure pit and penetrate the concrete pit walls.

Laboratory Results

Suspect Material Sampled	Location	Condition	Concentration % by Weight
White Fiberglass Tank	Sulfate Tank Coating	Intact	<0.0064%

Based on the sample analysis, none of the sampled coatings were found to contain Lead Based Paint.

Recommendations

A. Any demolition/renovation work in which lead coated surfaces are disturbed must be in compliance with all Federal, State, and Local regulations. All work should be conducted by workers trained in "lead safe practices" as outlined by OSHA.

B. If additional suspect materials are discovered during demolition/renovation, they should be classified presumed to contain lead-based paint until sampling by a state of North Carolina licensed Lead Inspector personnel and analysis by an Accredited and state of North Carolina licensed laboratory can be performed.

See attached for Plan Locations, Lead Laboratory Results, and Chain of Custody.

If further information is required, please contact me at 1-252-636-8778

Report Prepared by:

Christopher B. Walker
North Carolina Lead Inspector Accreditation# 110239
The Walker Group Architecture, Inc.
PO Box 541
New Bern, NC 28560

NC DEPARTMENT OF
HEALTH AND
HUMAN SERVICES

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK T. BENTON • Chief Deputy Secretary for Health
KELLY KIMPLE • Acting Director, Division of Public Health

August 18, 2025

Christopher B Walker
103 Conner Grant Rd
New Bern, NC 28562

Dear Mr. Walker:

The Health Hazards Control Unit (HHCU) has determined that you have fulfilled the application requirements and are eligible for lead certification as a(n) INSPECTOR. Your assigned Inspector certification number is 110239, which is reflected on your enclosed North Carolina Lead Certification card. The State requires that all persons conducting regulated lead-based paint activities be certified and have their identification card on-site.

A "Lead-Based Paint Activity Summary" shall be submitted to the HHCU by the certified inspector or risk assessor within 45 days of each inspection, risk assessment, or lead hazard screen conducted. The information shall be submitted on a form provided or approved by the Program, per 10A NCAC 41C .0807(b), Lead-Based Paint Hazard Management Program Rules.

Accredited refresher training must be completed at least every 24 months from the date of the last accredited training course **AND** within twelve months prior to applying for certification. The HHCU strongly recommends that individuals note the date of certification expiration and ensure all refresher training meets the above requirements.

Your North Carolina Inspector certification will expire on AUGUST 31, 2026. It is NOT the policy of the HHCU to issue renewal notices. If you wish to continue working as a(n) Inspector after this expiration date, you must successfully complete the required training and submit a completed application to this office prior to August 31, 2026. If you should perform lead-based paint activities as a(n) Inspector without a valid North Carolina certification, you will be in violation of State regulations and may be cited for noncompliance.

If you have any questions, please contact our office at (919) 707-5954.

Sincerely,

Ed Norman
Program Manager
Health Hazards Control Unit

Enclosure

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES . DIVISION OF PUBLIC HEALTH

LOCATION: 5505 Six Forks Road, Building 1, Raleigh, NC 27609
MAILING ADDRESS: 1912 Mail Service Center, Raleigh, NC 27699-1912
www.ncdhhs.gov . TEL: 919-707-5950 . FAX: 919-870-4808

AN EQUAL OPPORTUNITY / AFFIRMATIVE ACTION EMPLOYER

NC DEPARTMENT OF
HEALTH AND
HUMAN SERVICES

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK T. BENTON • Chief Deputy Secretary for Health
KELLY KIMPLE • Acting Director, Division of Public Health

July 1, 2025

Chris Walker
Walker Group Architecture Inc
409 Broad St
New Bern NC 28560-

Dear Walker:

Based upon the review of your Lead Firm Certification application, the Health Hazards Control Unit (HHCU) has determined that you have fulfilled the requirements and are eligible for Lead Firm Certification. Your assigned certification number is FPB-0329, which is reflected on your enclosed North Carolina Lead Firm Certification certificate.

Your North Carolina Firm Certification will expire on July 31, 2026. It is not the policy of the HHCU to issue renewal notices. If you wish to remain a certified firm after this expiration date, you must submit a completed application to this office prior to July 31, 2026. If you should continue to perform lead-based paint activities without a valid North Carolina firm certification, you will be in violation of State regulations and may be cited for noncompliance.

If you have any questions, please contact the HHCU at (919) 707-5950.

Sincerely,

Ed Norman
Program Manager
Health Hazards Control Unit

Enclosure

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES . DIVISION OF PUBLIC HEALTH

LOCATION: 5505 Six Forks Road, Building 1, Raleigh, NC 27609
MAILING ADDRESS: 1912 Mail Service Center, Raleigh, NC 27699-1912
www.ncdhhs.gov . TEL: 919-707-5950 . FAX: 919-870-4808

AN EQUAL OPPORTUNITY / AFFIRMATIVE ACTION EMPLOYER

Lead Survey
FC444 Aluminum Sulfate Tank Repairs
MCB Camp Lejeune

AIHA Laboratory Accreditation Programs, LLC

acknowledges that

EMSL Analytical, Inc.

706 Gralin Street Kernersville, NC 27284

Laboratory ID: LAP-102564

along with all premises from which key activities are performed, as listed above, has fulfilled the requirements of the AIHA Laboratory Accreditation Programs, LLC (AIHA LAP) accreditation to the ISO/IEC 17025:2017 international standard, General Requirements for the Competence of Testing and Calibration Laboratories in the following:

LABORATORY ACCREDITATION PROGRAMS

☐	INDUSTRIAL HYGIENE	Accreditation Expires:
☑	ENVIRONMENTAL LEAD	Accreditation Expires: June 01, 2026
☑	ENVIRONMENTAL MICROBIOLOGY	Accreditation Expires: June 01, 2026
☐	FOOD	Accreditation Expires:
☐	UNIQUE SCOPES	Accreditation Expires:
☐	BE FIELD/MOBILE	Accreditation Expires:

Specific Field(s) of Testing/Method(s) within each Accreditation Program for which the above named laboratory maintains accreditation is outlined on the attached Scope of Accreditation. Continued accreditation is contingent upon successful on-going compliance with ISO/IEC 17025:2017 and AIHA LAP requirements. This certificate is not valid without the attached Scope of Accreditation. Please review the AIHA LAP website (www.aihaaccreditedlabs.org) for the most current Scope.

Cheryl O. Morton

Cheryl O Morton
Managing Director, AIHA Laboratory Accreditation Programs, LLC

Revision21: 10/24/2023

Date Issued: 05/01/2024

EMSL Analytical, Inc.

706 Gralin Street, Kernersville, NC, 27284
Telephone: (336)-992-1025 Fax:(336)-992-4175

EMSL Order ID: 022650361
LIMS Reference ID: KE50361
EMSL Customer ID: WALK85

Attention: Chris Walker
The Walker Group Architecture [WALK85]
PO Box 541
New Bern, NC 28563
(252) 636-8778
chris@wgarc.com

Project Name: FC444 Aluminum Sulfate Tank Repairs
Project ID: 02-WALK85-LEAD
Customer PO:
EMSL Sales Rep: Jason McDonald
Received: 5/4/26 13:00
Reported: 05/07/26 07:38

Lead Interpretive Report

Analyte	Analyzed	Method	Reporting Limit	Units	Weight(g)	Results	Q	Indicator
Customer Sample ID: Pb01			Lab Sample ID: KE50361-01			**Collected:** 04/30/26 00:00		
Lead	05/06/26 08:16	SW 846-7000B	0.0064	% wt	0.253	<0.0064		✓
Site:								
Customer Sample ID: Pb02			Lab Sample ID: KE50361-02			**Collected:** 04/30/26 00:00		
Lead	05/06/26 08:17	SW 846-7000B	0.0064	% wt	0.2607	<0.0064		✓
Site:								

Interpretation Key and Definitions

✗ Above action level

! Above Reporting Limit (RL) but below action level

✓ Below Reporting Limit (RL)

These guidance limits are typically used in most scenarios. Other local or project specific guidelines may apply.
Please contact the laboratory for statement of uncertainty data for the utility of properly evaluating these results against any regulatory standards or guidelines.
No responsibility or liability is assumed for the manner in which the results are used or interpreted.

Guidelines for Federal USEPA/HUD Lead in Paint Chips
=0.5 % Wt or =1.0 mg/cm2 is the EPA definition of a lead-based paint.

James Cole

James Cole, Laboratory Manager or other approved signatory

Please visit our website at http://www.emsl.com
(c) 2023 EMSL Analytical, Inc. All rights reserved. No part of this report may be reproduced or otherwise distributed or used without the expressed written consent of EMSL.

Certified Analyses included in this Report

Analyte	Certifications
SW 846-7000B in Chips	
Lead	02-AIHA ELLAP

List of Certifications

Code	Description	Number	Expires
02-AIHA ELLAP	American Industrial Hygiene Association (AIHA LAP, LLC) - ELLAP	102564	06/01/2026
02-AIHA EMLAP	American Industrial Hygiene Association (AIHA LAP, LLC) - EMLAP	102564	06/01/2026

Please see the specific Field of Testing (FOT) on www.emsl.com <http://www.emsl.com> for a complete listing of parameters for which EMSL is certified.

Notes and Definitions

Item	Definition
(Dig)	For metals analysis, sample was digested.
[2C]	Reported from the second channel in dual column analysis.
DA	Direct Analysis
DF	Dilution Factor
MDL	Method Detection Limit.
ND	Analyte was NOT DETECTED at or above the reporting limit, or the mdl if provided.
NR	Spike/Surrogate showed no recovery.
Q	Qualifier
RCS	Respirable Crystalline Silica
RL	Reporting Limit
Wet	Sample is not dry weight corrected.

Measurement of uncertainty and any applicable definitions of method modifications are available upon request. Per EPA NLLAP policy, sample results are not blank corrected.

Please visit our website at http://www.emsl.com
(c) 2023 EMSL Analytical, Inc. All rights reserved. No part of this report may be reproduced or otherwise distributed or used without the expressed written consent of EMSL.

Lead (Pb) Chain of Custody

EMSL Order ID *(Lab Use Only)*: 152503601

EMSL ANALYTICAL, INC.
706 GRALIN STREET
KERNERSVILLE, NC 27284
336-992-1025

EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

Company : Walker Group Architecture	**EMSL-Bill to:** ☒ Same ☐ Different If Bill to is Different note instructions in Comments** *Third Party Billing requires written authorization from third party*
Street: 409 Broad St	
City: New Bern / **State/Province: NC**	**Zip/Postal Code: 28560** / **Country: US**
Report To (Name): Chris Walker	**Fax #:**
Telephone #: 252-636-8778	**Email Address: chris@wgarc.com**
Project Name/Number: FC444 Aluminum Sulfate Tank Repairs	
Please Provide Results: ☐ Fax ☒ Email	**Purchase Order:** / **U.S. State Samples Taken: NC**

Turnaround Time (TAT) Options* - Please Check

☐ 3 Hours	☐ 6 Hours	☐ 24 Hours	☐ 48 Hours	☒ 3 Days	☐ 4 Days	☒ 5 Days	☐ 10 Days

**Analysis completed in accordance with EMSL's Terms and Conditions located in the Price Guide*

Matrix	Method	Instrument	Reporting Limit	Check
Chips ☐ mg/cm² ☒ % by wt.	SW846-7000B/7420 or AOAC 974.02	Flame Atomic Absorption	0.01%	☒
Air	NIOSH 7082	Flame Atomic Absorption	4 µg/filter	☐
	NIOSH 7105	Graphite Furnace AA	0.03 µg/filter	☐
	NIOSH 7300 modified	ICP-AES	0.5 µg/filter	☐
Wipe* ☐ ASTM ☐ non ASTM *if no box is checked, non-ASTM Wipe is assumed	SW846-7000B/7420	Flame Atomic Absorption	10 µg/wipe	☐
	SW846-6010B or C	ICP-AES	0.5 µg/wipe	☐
TCLP	SW846-1311/7420/SM 3111B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	SW846-6010B or C	ICP-AES	0.1 mg/L (ppm)	☐
Soil	SW846-7420	Flame Atomic Absorption	40 mg/kg (ppm)	☐
	SW846-7421	Graphite Furnace AA	0.3 mg/kg (ppm)	☐
	SW86-6010B or C	ICP-AES	1 mg/kg (ppm)	☐
Wastewater	SM3111B or SW846-7000B/7420	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	EPA 200.9	Graphite Furnace AA	0.003 mg/L (ppm)	☐
	SW846-6010B or C	ICP-AES	1 mg/kg (ppm)	☐
Drinking Water	EPA 200.9	Graphite Furnace AA	0.003 mg/L (ppm)	☐

Other: / **Preservation Method (Water):**

Name of Sampler: Chris Walker / **Signature of Sampler:**

Sample #	Location	Volume/Area	Date/Time Sampled
Pb01	white fiberglass tank		04/30/2026
Pb02	white fiberglass tank		04/30/2026

Client Sample #'s Pb01 - Pb02 / **Total # of Samples:** 02

Relinquished (Client):	WGARC	**Date:**	05/01/2026	**Time:**	10 am
Received (Lab):	SEL	**Date:**	5/4/26	**Time:**	1:00 pm

Comments:

UPS-1Z 561 6W2 13 9216 0250

Asbestos Survey

FC444 Aluminum Sulfate Tank Repairs
MCB Camp Lejeune
Project # 25-0087

Report Prepared By:
Christopher B. Walker
The Walker Group Architecture, Inc
June 10th, 2026
WGA Project No. – 2609.SUFL

Project Information

The Walker Group Architecture, Inc. was contracted by NRW Engineering to conduct an asbestos sampling survey for FC444 Aluminum Sulfate Tank repairs project. The specified structure is slated for demolition and replacement of the tank and associated piping. An asbestos survey has been requested prior to disturbance of any potential asbestos containing materials (ACM).

Scope of Services

A. The survey was performed on 04/30/2026 by Christopher B. Walker (NC Accredited Inspector #12878, expires June, 2026). The sampling was conducted in general accordance with the U.S. Environmental Protection Agency (EPA) requirements as defined in the asbestos Hazards Emergency Response Act (40 CFR Part 763) guidelines (AHERA) and in general accordance with the North Carolina Health Hazards Control Unit (NCHHCU).

B. The survey was conducted to identify the presence of asbestos containing materials (ACM) prior to repairs to the building.

C. The building was assessed to determine homogenous areas (groups of materials appearing to have been installed in the same general time period and uniform in color and texture).

D. As per AHERA, sufficient samples were collected from random locations of each homogenous area, with the number of samples based on the following criteria:

- **a. Thermal Insulation Materials** (piping, breeching, boiler insulation, etc.) – A minimum of (3) samples are required. Patch areas (less than 6 square or liner feet) may have (2) sample collected.
- **b. Surfacing Materials** (plaster, fireproofing, etc.) – A minimum of (7) samples are to be taken for areas greater than 5,000 square feet, five (5) samples for areas greater than 1,000 square feet, but less than 5,000 square feet, three (3) samples for areas less than 1,000 square feet, two (2) samples for patching materials.
- **c. Miscellaneous Materials** (flooring, adhesives, roofing, wallboard, etc.) – A minimum of (2) samples are required.

If any one sample of a material from a homogenous area is found to be positive, then that material is considered positive, regardless of results of other samples of that material, within that area.

Samples

A. The Walker Group Architecture collected suspect samples and shipped them to EMSL Analytical, Inc. (NVLAP Accredited Laboratory 102104-0) for PLM (polarized Light Microscopy) analysis. In an effort to reduce cost, the Walker Group instructed the laboratory to Stop Analysis at the first positive sample for each suspect material HGA and not to analyze the remaining samples from the same HGA.

Building Description and Findings

FC444 Aluminum Sulfate Tank is a large fiberglass tank supported on a concrete pad. The tanks has several appurtenances and sets of piping that route around the tank enclosure pit and penetrate the concrete pit walls.
.

A. Laboratory Results

Material	Material Type	Location	Friability	Laboratory Result	Approx.Quantity
Miscellaneous Sealant	Misc	Pipe penetrations at concrete wall	NF	Non-Detected	N/A
Concrete Textured Coating	Surfacing	Concrete pit and slab coating	NF	Non-Detected	N/A

Based on the sample lab analysis none of the materials sampled were found to be Asbestos Containing Materials.

Disposal

A. In accordance with the NCHHCU regulations, asbestos containing materials (ACM) waste should be taken to an approved landfill. All demolition/renovation work must be performed in accordance with NESHAP asbestos regulations, 40CFR61, Subpart M, and OSHA Regulations 29 CFR 1926.1101. Any disturbance should be conducted in accordance with federal, state, and local regulations.

Recommendations

A. Any demolition/renovation work in which ACM is disturbed must be in compliance with, EPA, OSHA and the state of North Carolina regulations. Abatement work shall be conducted by NC Accredited asbestos workers under the supervision of a NC accredited asbestos supervisor. The contractor conducting asbestos abatement activities must notify the North Carolina Department of Health and Human Services (HHS) ten (10) days prior to the disturbance of ACM if it is friable and greater than or equal to 160 square feet, 260 linear feet or 35 cubic feet.

B. If additional suspect materials are discovered during demolition/renovation, they should be classified presumed to be asbestos-containing until sampling by a state of North Carolina licensed Asbestos Building Inspector personnel and analysis by a NVLAP-Accredited and state of North Carolina licensed laboratory can be performed.

See attached for Accreditations, Asbestos Lab Results and Chain of Custody. If further information is required, please contact me at 1-252-636-8778

Report Prepared by:

Christopher B. Walker, AIA
North Carolina Asbestos Inspector Accreditation# 12878
The Walker Group Architecture, Inc., PO Box 541, New Bern, NC 28560

NC DEPARTMENT OF
HEALTH AND
HUMAN SERVICES

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK T. BENTON • Chief Deputy Secretary for Health
KELLY KIMPLE • Acting Director, Division of Public Health

July 1, 2025

Christopher B Walker
103 Conner Grant Rd
New Bern, NC 28562

Dear Mr. Walker:

Based upon the review of your accreditation application, the Health Hazards Control Unit (HHCU) has determined that you have fulfilled the requirements and are eligible for asbestos accreditation as a(n) INSPECTOR. Your assigned North Carolina accreditation number is 12878, which is reflected on your enclosed North Carolina Accreditation card. Please be sure to take this card with you to any asbestos work site where you are employed. The State requires that all persons conducting asbestos abatement or asbestos management activities be accredited and have their identification card on site.

Your North Carolina Inspector accreditation will expire on JUNE 30, 2026. It is NOT the policy of the HHCU to issue renewal notices. If you wish to continue working as a(n) Inspector after this expiration date, you must successfully complete the required training and submit a completed application to this office prior to June 30, 2026. If you should continue to perform asbestos management activities as a(n) Inspector without a valid North Carolina accreditation, you will be in violation of State regulations and may be cited for noncompliance.

Sincerely,

Ed Norman
Program Manager
Health Hazards Control Unit

Enclosure

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES . DIVISION OF PUBLIC HEALTH

LOCATION: 5505 Six Forks Road, Building 1, Raleigh, NC 27609
MAILING ADDRESS: 1912 Mail Service Center, Raleigh, NC 27699-1912
www.ncdhhs.gov . TEL: 919-707-5950 . FAX: 919-870-4808

Asbestos Survey
FC444 Aluminum Sulfate Tank Repairs
MCB Camp Lejeune

United States Department of Commerce
National Institute of Standards and Technology

Certificate of Accreditation to ISO/IEC 17025:2017

NVLAP LAB CODE: 102104-0

EMSL Analytical, Inc.

Kernersville, NC

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2023-07-01 through 2024-06-30

Effective Dates

For the National Voluntary Laboratory Accreditation Program

EMSL Analytical, Inc.

706 Gralin Street Kernersville, NC 27284

Tel/Fax: (336) 992-1025 / (336) 992-4175

http://www.EMSL.com / kernersvillelab@emsl.com

EMSL Order: 022601777
Customer ID: WALK85
Customer PO:
Project ID:

Attention: Chris Walker
The Walker Group Architecture
PO Box 541
New Bern, NC 28563

Phone: (252) 636-8778
Fax: (252) 636-8992
Received Date: 05/04/2026 1:00 PM
Analysis Date: 05/04/2026
Collected Date:

Project: FC444 Aluminium Sulfate Tank Repairs

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

			Non-Asbestos		Asbestos
Sample	**Description**	**Appearance**	**% Fibrous**	**% Non-Fibrous**	**% Type**
01 *022601777-0001*	misc. sealant	Gray/Silver Non-Fibrous Homogeneous	<1% Cellulose <1% Synthetic <1% Glass	100% Non-fibrous (Other)	None Detected
02 *022601777-0002*	misc. sealant	Silver Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
03 *022601777-0003*	concrete textured coating	Tan/White/Yellow Non-Fibrous Heterogeneous	2% Cellulose <1% Synthetic <1% Glass <1% Hair	10% Ca Carbonate 88% Non-fibrous (Other)	None Detected
04 *022601777-0004*	concrete textured coating	Tan/White/Yellow Non-Fibrous Heterogeneous	2% Cellulose <1% Synthetic <1% Glass	10% Ca Carbonate 88% Non-fibrous (Other)	None Detected
05 *022601777-0005*	concrete textured coating	White Non-Fibrous Heterogeneous	2% Glass	5% Ca Carbonate 93% Non-fibrous (Other)	None Detected

Analyst(s)
Bobby Wheatley (2)
Scott Combs (3)

Stephen Bennett, Laboratory Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 “Interim Method”) but augmented with procedures outlined in the 1993 (”final”) version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. Kernersville, NC NVLAP Lab Code 102104-0, Virginia 3333-000228, West Virginia LT000321

Initial report from: 05/06/2026 14:44:42

OrderID: 022601777

EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

Asbestos Chain of Custody

EMSL Order Number *(Lab Use Only)*: 1777

EMSL ANALYTICAL, INC.
706 GRALIN STREET
KERNERSVILLE, NC 27284
PHONE: 336-992-1025
FAX: 336-992-4175

Company : Walker Group Architecture	EMSL-Bill to: ☒ Same ☐ Different If Bill to is Different note instructions in Comments**
Street: 409 Broad St.	*Third Party Billing requires written authorization from third party*
City: New Bern / State/Province: NC	Zip/Postal Code: 28560 / Country: US
Report To (Name): Chris Walker	Fax #:
Telephone #: 252-636-8778	Email Address: chris@wgarc.com
Project Name/Number: FC444 Aluminum Sulfate Tank Repairs	
Please Provide Results: ☐ Fax ☒ Email / Purchase Order:	U.S. State Samples Taken: NC

Turnaround Time (TAT) Options* – Please Check

☐ 3 Hours ☐ 6 Hours ☐ 24 Hrs ☐ 48 Hrs ☒ 3 Days ☐ 4 Days ☐ 5 Days ☐ 10 Days

**For TEM Air 3 hours/6 hours, please call ahead to schedule.*There is a premium charge for 3 Hour TEM AHERA or EPA Level II TAT. You will be asked to sign an authonzation form for this service. Analysis completed in accordance with EMSL's Terms and Conditions located in the Analytical Price Guide.*

PCM - Air
- ☐ NIOSH 7400
- ☐ w/ OSHA 8hr. TWA

PLM - Bulk (reporting limit)
- ☒ PLM EPA 600/R-93/116 (<1%)
- ☐ PLM EPA NOB (<1%)

Point Count
- ☐ 400 (<0.25%) ☐ 1000 (<0.1%)

Point Count w/Gravimetric
- ☐ 400 (<0.25%) ☐ 1000 (<0.1%)
- ☐ NYS 198.1 (friable in NY)
- ☐ NYS 198.6 NOB (non-friable-NY)
- ☐ NIOSH 9002 (<1%)

TEM - Air
- ☐ AHERA 40 CFR, Part 763
- ☐ NIOSH 7402
- ☐ EPA Level II
- ☐ ISO 10312

TEM - Bulk
- ☐ TEM EPA NOB
- ☐ NYS NOB 198.4 (non-friable-NY)
- ☐ Chatfield SOP
- ☐ TEM Mass Analysis-EPA 600 sec. 2.5

TEM – Water: EPA 100.2
- Fibers >10µm ☐ Waste ☐ Drinking
- All Fiber Sizes ☐ Waste ☐ Drinking

TEM- Dust
- ☐ Microvac - ASTM D 5755
- ☐ Wipe - ASTM D6480
- ☐ Carpet Sonication (EPA 600/J-93/167)

Soil/Rock/Vermiculite
- ☐ PLM CARB 435 - A (0.25% sensitivity)
- ☐ PLM CARB 435 - B (0.1% sensitivity)
- ☐ TEM CARB 435 - B (0.1% sensitivity)
- ☐ TEM CARB 435 - C (0.01% sensitivity)
- ☐ EPA Protocol (Semi-Quantitative)
- ☐ EPA Protocol (Quantitative)

Other:
- ☐

☒ **Check For Positive Stop – Clearly Identify Homogenous Group**

Samplers Name: Chris Walker | Samplers Signature:

Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
01	misc. sealant	HA01	04/30/2026
02	misc. sealant	HA01	04/30/2026
03	concrete textured coating	HA02	04/30/2026
04	concrete textured coating	HA02	04/30/2026
05	concrete textured coating	HA02	04/30/2026

Client Sample # (s): 01 - 05 Total # of Samples: 05

Relinquished (Client): WGARC Date: 05/01/2026 Time: 11:00am

Received (Lab): Date: 5/4/26 Time: 1:00 pm

Comments/Special Instructions:

UPS - 12 561 6W2 13 9216 0250

Controlled Document – Asbestos COC – R1 – 3/18/2009

Page 1 of 1 pages