Pre-Proposal Site Visit for Solicitation #140P8326R0006

July 27, 2026

1. Can you clarify the dates in Section 01 11 00, Part 1 – General, item 2?
    a. The Period of Performance is from 09/01/2026 to 12/31/2027.
        i. Reservations for the 2026 season end 09/29/2026.
            1. No Work in the campground is allowed during reservation season. Some staging of materials may be allowed with close coordination with COR
        ii. Campground closed 10/05/2026 – 04/23/2027
            1. Contractor has exclusive use of Campground
        iii. Campground open with no reservation system 04/24/2027 – 05/14/2027
            1. NPS can keep Loop A Closed for contractor to have exclusive use of Loop A. No other work to take place outside of Loop A.
        iv. Campground open with Reservation System 05/15/2027 – 09/28/2027
            1. No work in the campground is allowed.
        v. Campground closes 10/05/2027 for the season
            1. Contractor has exclusive use of the campground till the end of the Period of Performance
2. The contractor must have a hazardous material spill kit on site at all times.
3. Is the contractor responsible for surveying and construction staking?
    a. Yes
4. What types of third party testing are required?
    a. Compaction testing on import subgrade material is required on the slabs, sidewalks, and under asphalt patches, locations to be chosen at random by third party tester.
5. Will there be utilities available at the campground during the construction windows?
    a. XXXX
6. What is the contractor's responsibility for the sites during the campground reservation season when no work is allowed?
    a. Both comfort stations need to be left in a state where they can be operational and open to the public. Certain areas that are in mid-construction need to be left in a safe manner for the public. For example, family restroom sites or concrete features left in mid construction shall be secured with temporary fencing or other methods approved by the COR to render the area safe for the public.
7. Is the contractor building the vertical structure of the family restroom?

   a. No, the contractor is doing the flat work. A park crew will finish building the family restroom at a later date.

8. Can Bearicuda Bins be an approved substitute for the Haul-All Bear Food Storage Bins?
   a. Yes, Bearicuda Bins https://bearicuds.com/ are an approved substitute. The approved alternative is the Whistler 16 CU FT. Bear Resistant Food Storage Locker – Two Door (LOC101D) in Color Brown with none of the options.

United States Department of the Interior

NATIONAL PARK SERVICE
PWR Regions 8,9,10 and 12, Olympic MABO
810 State Route 20
Sedro-Woolley, WA. 98284

CONTRACTING OFFICE

SITE VISIT SIGN-IN SHEET

PARK: Olympic NP

PROJECT TITLE: Rehabilitate Fairholme Campground Comfort Stations A & B for ABA Access

RFQ #140P8326R0006

DATE: July 27, 2026

TIME: 10:00 AM PST

LOCATION: Fairholme Campground, Olympic National Park, Port Angeles, WA 98363

Name	Nick Morrigan
Signature	
Company	Jamestown Excavating
Phone	360-809-8737
E-mail	nmorrigan@jamestowntribe.org

Name	Tim DeMyer
Signature	
Company	Jamestown Concrete
Phone	918-504-4151
E-mail	tdemyer@gmail.com

Name	Tommy Wood
Signature	
Company	Tom Wood Concrete
Phone	360-477-0778
E-mail	TomWoodConcrete@hotmail.com

Name	Todd Northern
Signature	
Company	2 Grade LLC
Phone	360 461-3988 / Greg 461-3992
E-mail	two-grade@hotmail.com