Bid Sheet – Reading Island Pavement Repairs

Bureau of Land Management 2026

CLIN	Description	Quantity	Unit	Unit Cost	Total Cost
0001	Mobilization	1	**LS**		
0002	Full Depth Repairs	4000	**SF**		
0003	Surface Preparation	90000	**SF**		
0004	F&S Tack Coat	94000	**SF**		
0005	HMA Overlay • 1/2-inch NMAS, PG 64-10 • Placed in two lifts • 0.10 ft compacted thickness per lift	94000	**SF**		
0006	Shoulder Backing	5400	**LF**		
0007	Compaction Testing – 3 tests • Site Road – front • Parking Lot • Site Road - back	3	**EA**		
0008	Site Restoration, cleanup, demobilization	1	**LS**		
-	**TOTAL COST**	**-**	**-**	**-**	