Question: Do you have any drawings or specifications?

Answer: No

Question: Island Workstation Configuration (1 EA):

- Overall Dimensions: 192"'W"×60"'D"×36"'H" comprising 8 station areas with knee holes and (1) 18'' suspended drawer/cabinet per station.

    1. Presume these are 48”W each table back to back. Yes
    2. Do they have shelving system? No
    3. Is there any fixtures? No
    4. Something like these? Yes, BasikBench and right side showing back to back with floating cabinet, no shelving.

    5. Do they need casters? No

Question — Optional Right-Side Sink Table Workstation (1 EA):

Dimensions: (1) Sink table (60"'W"×30"'D"×36"'H") attached to (1) table (60"'W"×30"'D"×36"'H") on left.

- Is this a table or a fixed base cabinet? Table
- Features: 1'' black epoxy resin top with 4'' backsplash, 4'' back-edge overhang for wall piping, drop-in sink (24"'W"×18"'D"×11"'H"), deck-mounted mixing faucet, single faucet, and swing-down eyewash station.
    - Please advise what “Single” faucet means? Cold water only? Single faucet is usually a RO or distilled water only. Picture is for reference only.

- Please confirm the sink will have 2 total faucets. Yes

Question: Is there a loading dock? No loading dock. Lift gate service will be required.

Question: Can you advise what floor the project is on? 2nd, elevator is accessible.

Question: Are there any BIM requirements? No

Question: Normal working hours? These are stated in the solicitation's statement of work

Question: Any requirements like US citizens only? All of the contractor's employees will need to be able to access Ft. Detrick. See https://home.army.mil/detrick/my-fort/visitors