Statement of Work

For

60 OSS/OSL Composite Tool Kit (CTK) Workstations

28 July 2026

The 60th Operations Support Squadron (OSS) / Operations Support Logistics (OSL), Travis AFB, CA has a requirement for contractors to provide Composite Tool Kit (CTK) Workstations and remove 1 high density mobile storage system in order to support the maintenance of Aircrew Flight Equipment.

Description: The contractor shall provide 11 CTK Workstations in accordance with OSHA standards. For visual references of the required workstation layout and design expectations, see **Attachment 1**.

1. Workstation Specifications & Measurements
The workstations must incorporate the following structural and dimensional requirements (see **Attachment 1** for visual guidance):

- **Dimensions:** 72” (H) x 80.75” (W).
- **Storage:** A minimum of three standard drawers and one large drawer to support both standard and non-standard tools.
- **Surface:** The surface top of the workstation must be constructed of a non-splintering material (metal or butcher block wood) and topped with half-inch absorbing padding.
- **Hanging Support:** A single horizontal rail system constructed of one-inch metal piping, used to support the hanging of equipment, must be suspended above the workbench surface top.
- **Electrical/Lighting:** A horizontal LED lighting system with a dual 110v power outlet and breaker is required.
- **Mobility:** Wheels with a locking function must be incorporated to assist with repositioning.

2. Contractor Provided Services & Installation
2.1 All freight, handling, and labor charges must be included in the final quote.
2.2 Assembly and installation of CTK Workstations must be completed by a trained professional.
2.3 Labor, installation, and set-up must be performed between the hours of 7:00 AM - 4:00 PM, Monday through Friday.
2.4 Must include all additional accessories, provided at the time of set-up.
2.5 Must provide time for AFE personnel to inspect the CTK Workstations upon completion of assembly to ensure standards have been met, and to provide any concerns or repair recommendations.

3. Warranty:
Contractor will provide an equipment warranty of no less than 12 months following the receipt of the CTK Workstations. The warranty shall include the replacement and removal of any worn or broken parts.

4. Delivery Address & Access:
Delivery to Travis AFB, CA. Delivery drivers must be able to obtain an installation pass for base access.