PROJECT DESCRIPTION

The work includes replacement of the existing roofing system at building 1771. The contractor shall demo approximately 15,300 sf existing roof system and install a new roof system to include new metal cap, flashing, pitch pockets, lead vent covers, drain systems, drain covers, and incidental related work.

SPECIAL SCHEDULING

The facility/activity will remain in operation during the entire construction period. The Contractor shall conduct his operations so as to cause the least possible interference with normal operations of the facility/activity.

SUPERVISION

One person may fill the roles of Superintendent, Quality Control Manager, and Safety & Health Officer, if duly qualified for all three positions as defined in the project specification.