DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 341ST MISSILE WING (AFGSC)

29 July 2026

SYNOPSIS

TITLE: Repair HICS Gates
Classification Code: Z2JZ
NAICS Code: 238990
Primary POC: Elizabeth Basu, elizabeth.basu@us.af.mil
Secondary POC: Colleen Goad, colleen.goad.1@us.af.mil
Solicitation Number: FA4626-26-R-0010

DESCRIPTION:

The purpose of this project is to remove, replace, and repair designated livestock gates within the 341st Missile Complex. The scope of work requires the Contractor to cut existing fence lines and install new gates in areas where property owners currently have wire over gates. Alternatively, the Contractor may be directed to temporarily cut the fence for access and repair it with a splice after the work party has proceeded through the right-of-way. All actions require the Contractor to install a fluorescent delineator coil and transfer any existing metal Government Number Tags to the new posts. The Contractor shall furnish all labor, materials, equipment, and supervision necessary to accomplish these tasks.

Due to the sensitive nature of the operational area, specific excavation safety controls are mandatory. The Contractor must perform all digging by hand within three feet of any buried communications cables, electrical cables, or gas lines until the utility is fully exposed. All cable and piping routes must be formally marked prior to beginning any excavation in the area. Furthermore, the Contractor must obtain an approved Work Clearance Permit (AF Form 103) from Missile Engineering before commencing any excavation work. The 341st Missile Complex consists of 15 distinct flights dispersed within a 160-mile radius of Great Falls, Montana. The project worksites will be grouped in such a manner that all gates will be completed in one flight before starting the next flight to keep mobilization distances to less than 10 miles between gates. Further project details and information will be provided via a Statement of Work.

A single firm fixed price five (5) year Indefinite Delivery Indefinite Quantity (IDIQ) contract will be awarded for this HICS Gates project. The Request for Proposal will be posted and available no sooner than **12 August 2026**. This acquisition is set aside for Service-Disabled Veteran Owned Small Businesses (SDVOSB). The Request for Proposal will only be available via Electronic Transmission on the System for Award Management (SAM) website (http://www. SAM.gov).

Potential contractors must be registered as an SBA Certified SDVOSB on SAM.gov **to be eligible for award.**

Place of Performance: Malmstrom, AFB MT, 59402, U.S.
Set Aside Information: Service-Disabled Veteran Owned Small Business (SDVOSB).