Solicitation No : 19MY3026Q0020

Questions And Answers

Date : 31 July 2026

Question 1: Could you please confirm the basis for award? Specifically, will award be made to the Lowest Price Technically Acceptable (LPTA) quotation, or on a Best Value basis using technical and price evaluation factors?

Answer 1: LPTA

Question 2: Photo External View 1 – THE WALL OUT SIDE the room need to retiled as well?

Answer 2: Yes, wall outside is the open shower. The existing tiles will need to be replaced.

Question 3: Photo External View 2 - THE WINDOWS shown in visualization look different from the existing, are existing windows to be replaced with one single pieces fixed glass?

Answer 3: The sample view of final product is for visual reference on the finishing only. No replacement is required for the existing windows.

Question 4: Are the Exhaust fans new (or replace existing? – for wiring purposes). Are they wall mounted or ceiling mounted?

Answer 4: There are currently only ceiling fans and no exhaust fan. Window-mounted exhaust fans and wall-mounted fans are required for ventilation.

Question 5: Could you provide the **size** of SHELF Cabinets? And the proposed **location** in the rooms? (please indicate on the floor layout?

Answer 5: Minimum 38x38x180-cm (WxDxH), to be installed against the side wall.

Question 6: What material for the SHELF Cabinets is required? **METAL or WOOD**

Answer 6: Metal.

Question 7: What is the size of Seating Benches?

Answer 7: Minimum 120x40x45-cm (WxDxH).

Question 8: Is there any work inside PUMP room? We assume it only painting on the exterior.

Answer 8: No work is required inside the pump room. Only exterior wall painting is required.