PRODUCT SPECIFICATIONS (Or Equivalent)

NAME	LOCATION	MANUFACTURER	MODEL	COLOR	SIZE
PAINT	PRIMARY WALLS	BENJAMIN MOORE	1548	CLASSIC GRAY	-
ACCENT PAINT	SLEEPING ROOMS	BENJAMIN MOORE	1552	RIVER REFLECTIONS	-
PAINT	DOOR FRAMES	SHERWIN WILLIAMS	SW 7026	GRIFFIN	-
PAINT	GWB & EXPOSED CEILINGS	SHERWIN WILLIAMS	SW 7102	WHITE FLOUR	-
WALL GRAPHIC	LOUNGE	FIND YOUR LEVEL	LINDSEY II	BEIGE	-
LUXURY VINYL TILE	SLEEPING ROOMS	MANNINGTON	CRISSCROSS	ZOOM CHARCOAL	-
LUXURY VINYL TILE	OFFICES	MANNINGTON	ACCESS STONE	LINEAR STONE SHALE	-
RUBBER BASE	PRIMARY BASE	JOHNSONITE	283	TOAST	-
TRANSITION STRIP	LVT TO TILE	SCHLUTER	RENO-U AEU 35	SATIN ANODIZED	-
TRANSITION STRIP	LVT TO CONCRETE OR EPOXY	SCHLUTER	RENO-U AEU 100	SATIN ANODIZED	-
CORNER GUARD	OUTSIDE CORNERS	INPRO	TYPE 430	STAINLESS STEEL	-
EPOXY RESINOUS FLOORING	LOUNGE & SHARED SPACES	DUR-A-FLEX	DUR-A-QUARTZ	Q28-23	-

GENERAL NOTES

- FINISHES INDICATED ARE THE APPROVED BASIS OF DESIGN TO CONVEY COLOR, PATTERN, TEXTURE AND SALIENT CHARACTERISTICS ONLY. THE LISTING OF MANUFACTURER INFORMATION IS NOT INTENDED TO LIMIT THE SELECTION OF PRODUCTS PROVIDED BY OTHER MANUFACTURERS. PRODUCTS MEETING THESE CRITERIA WILL BE CONSIDERED AND MUST BE REVIEWED BY THE PROJECT MANAHGER AND APPROVED BY THE NAVFAC CONTRACTING OFFICER. FINISH ITEMS ARE NOT TO BE SUBSTITUTED DUE TO ORDERING LEAD TIMES. IT IS THE CONTRACTOR 'S RESPONSIBILITY TO ORDER ALL MATERIALS IN TIME TO AVOID DELAYS.
- FINISH ITEMS ARE NOT TO BE SUBSTITUTED DUE TO ORDERING LEAD TIMES. IT IS THE CONTRACTOR 'S RESPONSIBILITY TO ORDER ALL MATERIALS IN TIME TO AVOID DELAYS.
- ALL INTERIOR FINISHES IN VERTICAL EXIT WAYS, EXIT LOBBIES, AND EXIT CORRIDORS MUST MEET MINIMUM CLASS A RATING.
- SPRAY PAINT ELECTRICAL PANELS, ACCESS PANELS, AND EXPANSION JOINTS TO MATCH THE ADJACENT WALL COLOR. PANELS PAINTED BY BRUSH ARE NOT ACCEPTABLE.
- ALL MATERIALS/PRODUCTS ARE TO BE INSTALLED PER MANUFACTURER'S INSTALLATION REQUIREMENTS.
- ALL FLOORING TRANSITIONS MUST MEET ABA GUIDELINES. FLOORING TRANSITIONS OCCURRING UNDER DOORS MUST BE CENTERED UNDER DOOR.

ROOM FINISH SCHEDULE (AS Applicable)

NAME	FLOOR FINISH	BASE FINISH	WALL FINISH	CEILING FINISH	NOTES
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
CLERKS OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
LAUNDRY	SC-1	RB-1	PNT-1	PNT-6	
STOR	SC-1	RB-1	PNT-1	PNT-6	
STORAGE	SC-1	RB-1	PNT-1	PNT-6	
VENDING	SC-1	RB-1	PNT-1	PNT-6	
OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
CORRIDOR	SC-1	RB-1	PNT-1	PNT-6	
LAUNDRY	SC-1	RB-1	PNT-1	PNT-6	
ADMINISTRATIVE OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
ELEC	SC-1	RB-1	PNT-1	PNT-6	
ADMINISTRATIVE OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
CO OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
STOR	SC-1	RB-1	PNT-1	PNT-6	
STORAGE	SC-1	RB-1	PNT-1	PNT-6	
WOMENS	T-1	-	T-2, T-3	PNT-6	1, 3
MENS	T-1	-	T-2, T-3	PNT-6	1, 3
COPY/ KITCHENETTE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
XO OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
LAUNDRY	SC-1	RB-1	PNT-1	PNT-6	
JANITOR	SC-1	RB-1	PNT-1	PNT-6	2
STORAGE	SC-1	RB-1	PNT-1	PNT-6	
VENDING	SC-1	RB-1	PNT-1	PNT-6	
COMM	SC-1	RB-1	PNT-1	PNT-6	
CORRIDOR	SC-1	RB-1	PNT-1	PNT-6	
LOUNGE	RES-1	RES-1	PNT-1, WC-1	PNT-6	
ELEC	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL	SC-1	RB-1	PNT-1	PNT-6	
LAUNDRY	SC-1	RB-1	PNT-1	PNT-6	
JANITOR	SC-1	RB-1	PNT-1	PNT-6	2
STORAGE	SC-1	RB-1	PNT-1	PNT-6	
VENDING	SC-1	RB-1	PNT-1	PNT-6	
OFFICE	LVT-2	RB-1	PNT-1, PNT-3	PNT-6	
CORRIDOR	SC-1	RB-1	PNT-1	PNT-6	
LOUNGE	RES-1	RES-1	PNT-1, WC-1	PNT-6	
ELEC	SC-1	RB-1	PNT-1	PNT-6	

MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
MECHANICAL CHASE	SC-1	RB-1	PNT-1	PNT-6	
TYPICAL SLEEPING ROOM	LVT-1	RB-1	PNT-1, PNT-2	PNT-6	4
TYPICAL BATH	T-1	-	T-2, T-3	PNT-6	1, 3