Ship/HULL NO.	Ship/HULL NAME	JON:	ICN:	Rev:	Key Op:
YON-285	BARGE		89MVA86303		A01

TITLE:

Temporary Head; provide

JOB SPECIFICATION

Anticipated Award Date:	Production Completion Date:	PREPARING ACTIVITY:
7/31/2026	02/02/2027	SASEBO
POP Start Date: 9/28/2026	**POP End Date:** 4/30/2027	

PREPARED BY: **H. MUTA**	CODE **H_MU**	DATE **1/23/2026**
APPROVED BY: **S. MURAKAMI**	CODE **S225**	
CONCURRED BY: **S. MOROOKA**	CODE **S231**	
ASSIST PLANNER'S NAME:	CODE	
ASSIST PLANNER'S NAME:	CODE	
ASSIST PLANNER'S NAME:	CODE	

DESCRIPTION:

JSN(S): N/A **CASREP #** .

S/F CONTACT: N/A **CWP #** **CCNS #** .

T. ESCRITOR-YAMADA
PM S320

Approved by S300/S900 **Date:** 2/2/2026 **Avl:** ~~7B1~~ 6B1 .

LWC: .

Work Completed

S/Force: **Rate:** **Date:** .

Ship Supt: **Date:** **SRF CONTROL NO.:** 1301348511 .

WORK CERTIFICATION SIGNATURES

COMPLETION OF WORK REVIEW:	BADGE NO.:	SHOP/CODE:	PHONE:	DATE:

Ship/HULL NO.	Ship/HULL NAME	JON:	ICN:	Rev:	Key Op:
YON-285	BARGE		89MVA86303		A01

TITLE:

Temporary Head; provide

1. **SCOPE:**

1.1 Title: Temporary Head; provide

1.2 Location of Work:

1.2.1 Alongside of the Barge

1.3 Identification:

1.3.1 Quantity (2 EA), Temporary Portable Head for ~~Mail~~ Male Use, Each Consists of One Water Closet (Western Type), Sewage Accumulating Tank and Door with Locking Device Located in 1.2.1

1.3.2 Quantity (One EA), Temporary Portable Heads for Female Use, Each Consists of One Water Closet (Western Type), Sewage Accumulating Tank and Door with Locking Device Located in 1.2.1

1.3.3 Quantity (One EA), Portable Washbasin with Mirror and Foundation (Approximately Foundation Height: 300 Millimeter) Located in 1.2.1

2. **REFERENCES:**

2.1 None.

3. **REQUIREMENTS:**

3.1 Provide and maintain each temporary portable head and washbasin listed in 1.3.1 through 1.3.3 at each location designated by SHIPSUPT during the availability.

3.1.1 Each door must have locking device that can be operated from inside.

3.1.1.1 Install each label plate indicated in both ENGLISH and JAPANESE letters as FOR MALE USE on each door of head listed in 1.3.1.

3.1.1.2 Install each label plate indicated in both ENGLISH and JAPANESE letters as FOR FEMALE USE on each door of head listed in 1.3.2.

3.1.2 Provide each hose for the heads and washbasin.

3.1.3 Provide each toilet paper and soap during period for the temporary portable heads and washbasin.

3.1.4 Clean each temporary head and washbasin two times a day.

3.1.5 Apply Approximately 200 cubic centimeters (CC) of disinfectant (deodorizer) to each head (urinals and toilet bowls) to keep clean sanitary condition.

3.1.6 Application of the disinfectant (deodorizer) must be made using materials such as creosote two times a day after clean up.

3.1.7 Each temporary head and washbasin must be secured to prevent from damage against bad weather and set up properly (flat level and height).

3.2 Collect, transport and dispose of the sewage (estimated 4,188 gallons) accumulated in each temporary head and drain water from washbasins listed in 1.3.1 through 1.3.3 in accordance with Japan Environmental Governing Standards (JEGS).

(V) "REPORT"

3.2.1 Submit one legible copy of a report listing the amount of sewage discharged actually to SUPERVISOR after disposal of the sewage.

3.2.1.1 The report must be written in English and unit for the amount of the sewage must be in Gallon.

3.3 Remove each portable head and washbasin listed in 1.3.1 through 1.3.3 when notified by SHIPSUPT.

4. NOTES:

4.1 Initial Condition - Temporary heads are required for a period of 7B1 availability.

5. GOVERNMENT FURNISHED MATERIAL(GFM) :

5.1 None.