Shasta-Trinity National Forest
McCloud Ranger District
Ash Creek Helispot - Phase 1
SCHEDULE OF ITEMS - UPDATED 7/22/2026

7/22/2026

Total Base Items

Item	Description	Estimated Qty	Unit	Unit Price	Total Price
A	Mobilization	1	LS		
B	Clearing and Grubbing	7	AC		
C	Overexcavation, Subgrade Preparation, Fill Placement and Grading	6700	CY		
D	Furnish and Place Class 2 Aggregate Base	500	CY		
E	Construct Reinforced Concrete Helipad	19	CY		
F	Paint Helipad Designation Markings	1	LS		
G	Furnish and Install 3" Sch 80 PVC Pipe & Fittings	492	LF		
H	Join Existing 3" Water Line per Detail 1, Sheet 7	1	LS		
I	Furnish and Install Fire Hydrant Lateral with Gate Valve and Swing Check Valve per Details 4 and 5, Sheet 7	2	EA		
J	Furnish and Install 3" Gate Valve & Stub per Detail 4, Sheet 7	1	LS		
K	Construct Connection to 4" CIP per Detail 2, Sheet 7	1	LS		
L	Remove Existing 3" Gate Valve per Detail 3, Sheet7	1	LS		
M	Furnish and Install 3" Gate Valve, 3" Double Check Valve and Insulated DC Valve Enclosure per Detail 6, Sheet 7.	1	LS		
N	Furnish and Install Water Line Marker per Detail 7, Sheet 7.	2	EA		
O	Pressure Test/Leak Test Water Line	1	LS		
P	Disinfect, Sample & Test Potable Water System	1	LS		
Base Bid Total					

Option Items (Gravel Helipad Loop Road & Install Electrica/Communicationsl Conduit)

Item	Description	Estimated Qty	Unit	Unit Price	Total Price
Q	Furnish and Place Class 2 Aggregate Base	300	CY		
R	Furnish and Install Electrical and Communications Duct Bank	260	LF		
Option Bid Total					
Bid Total					