C - Description/Specifications

Clauses

The objective of this project is to replace the failed primary and secondary control valves and modify the manifold valve piping at the Park Center Well as shown in the contract drawings and specifications attached. The project requires a specialized "live-well" intervention to manage 200 PSI artesian flow without a functional primary shut-off. Work includes pressure control, manifold valve modification for future rig connectivity, and strict adherence to environmental discharge permits.