Section B - Supplies or Services/Prices was revised as follows.

Clauses was revised as follows.

BID SCHEDULE

Each Bid item shall include all cost for materials, labor, expenses, fees, and taxes plus permitting costs, overhead and profit associated with each bid item to construct the following areas of work in accordance with the contact documents. The unit costs shall include the costs for all construction disciplines (civil, structural, mechanical, electrical, control work, etc) associated with the work area. Additive Alternates Bids will be awarded as available funds allow.

SCHEDULE OF
ITEMS

Request for Proposal No. Contract No.

Job Title: Park Center Well Main Valve Replacement
BUREAU OF LAND MANAGEMENT, COLORADO

Furnish all necessary labor, equipment, supervision, supplies and materials to provide items listed below in accordance with the Scope of Work provided and all other provisions contained herein. Include all accessories and incidental items necessary to render the project fully operational in accordance with the scope of work.

Item No.	Description	Est. Quantity	Unit	Unit Price	Total Amount
1	Mobilization & Administrative Submittals - The Contractor shall prepare and submit all required technical plans for Government review and approval within specified timeframes prior to initiating physical site construction.	1	L.S.		
2	Permitting & Environmental Compliance - The Contractor shall secure all applicable regulatory permits, strictly manage water discharge in accordance with state dilution criteria.	1	L.S.		
3	Flow Control & Well Isolation (Contractor¿s Risk) - The Contractor shall design, implement, and maintain the live-well isolation mechanism and assume full, unconditional liability for well containment and blowout prevention.	1	L.S.		
4	API 6A Christmas Tree Installation & Valve Replacement - The Contractor shall furnish and install the complete API 6A Christmas tree assembly and connect the new production valve directly to existing water district delivery piping.	1	L.S.		

5	Building Height Modification, Hydronic Heating & Gas Detection Systems - The Contractor shall design, modify, and install the structural building extension, radiant geothermal heating system, solar power integration, and hazardous gas monitoring network.	1	L.S.
6	Testing, Quality Control & NSF System Certification - The Contractor shall perform hydrostatic pressure testing on the replaced Christmas tree assembly and certify full functionality of safety systems.	1	L.S.
7	Building Reset, Site Restoration & Structural Anchoring - The Contractor shall safely reset and anchor the modified building onto the foundation, integrate all weatherproofing, and restore surrounding site drainage to as-new conditions.	1	L.S.
8	Hazardous Waste & Arsenic Scale Debris Disposal -The Contractor shall take ownership of all removed wellhead components and legally transport and dispose of all debris at a licensed facility in compliance with CDPHE hazardous waste regulations.	1	L.S.

Contract Total

Total (All or None)
Total (Written):

CONTACT INFORMATION:
POC NAME:
COMPANY NAMTE/ADDRESS:
UEI:

- END OF BID SCHEDULE -