1) Please provide data sheets for the existing products.

Please refer to Attachments Named: Updated SOW, Attachment 4 and Attachment 5 for detailed specification and Installation guide. Also please refer to Question 2

2) Please provide photographs of all work elements, including existing granite panels, pavers, ceilings, walls, painted surfaces, Consulate seals, logos, moldings, trims, and all other areas requiring repair.

ST-3 MG4 Ghibli Granite Grey Polished

ST-6 Ghibli Granite Colour Honed finished

(Qty 2500 sqft) Envi Crete Flat Paver grey colour (450 mm x 300 mm x 40mm) 3000PSI pavers (Red colour)12-inch x 12-inch x 40mm (Qty req 200 each) 3000PSI



Envi Crete Boston

Please refer to the Attached Pictures. Details sizes with required quantity mentioned below:

ST-3 Ghibli Granite Grey:

1130 mm (Width) x 700 mm (Height) x 40 mm (Qty 02)

1140 mm (Width) x 700 mm (Height) x 40 mm (Qty 03)

45.5 inch (Width) x 6 inches (Height) x 3 inches (Tapered) x 400mm thick. (Qty 03)

1540 mm (Width) x 180 mm (Height) x 40mm (Qty 02)

ST-6 Ghibli Granite Honed finished:

980mm (Height) x 1230 mm (Width) x 40mm (Qty 01)

1130 mm (Width)x 980 mm (Height) x 40mm (Qty 03)

3) Please provide the total paintable surface area (square feet or square meters) for all walls, ceilings, and other surfaces included in the finishing works as specified under Task 4 –Finishing Works.

The total area is 800 SQFT. It is already mentioned in attachment 3 sub-section 9, Vendor needs to submit high quality exterior ceiling weather shied white paint sample (like Jotun).

4) The RFQ requires work to commence within 10 calendar days after NTP and complete within 30 calendar days. Please confirm whether the 30-day duration starts after all worker security clearances and access badges are issued.

30 days will start when the vendor starts commencement to work at site

5) Will the Government provide access to water, electricity, storage area, staging area, and waste collection area on site?

Yes, Consulate will provide access.

6) Please confirm which material samples must be submitted before starting work, including granite, pavers, cement board, adhesive, grout, sealant, primer, and paint.

All the items sample should be provided for clearance before the commencement of work along with necessary test certification for pavers and granite

7) What is the expected review time for material samples and product data submitted?

Estimated approval time will be 7 working days.

8) Please confirm whether a U.S.-based small business registered in SAM.gov may submit as the Prime Contractor for this RFQ while using a qualified local Karachi-based subcontractor with a C-4 license to fulfill the requirement as specified in solicitation document. Would this arrangement be acceptable?

Yes, you may hire a subcontractor, provided your technical proposal clearly outlines all subcontracting details, including scopes, specific duties, and division of labor. The prime contractor must self-perform a minimum of (50%) of the total work. Ensure your own roles and responsibilities are explicitly defined in the proposal.

9) Please confirm how payment would be processed if the Prime Contractor is a U.S.-based SAM-registered company. Since the RFQ pricing is requested in PKR, please clarify whether payment can be made to our U.S. bank account listed in SAM.gov, or whether the Government requires payment to be made locally in Pakistan through a Pakistani bank account.

Payment can be made in USD if the contractor has a valid and active USD account. Furthermore, for USA Companies, they can quote in USD and for Pakistani Companies, they should quote in PKR.

10) Could you please provide the paver specifications, including the type, and any manufacturer or product requirements?

Please refer to the answer of Question 1

11) Can you please confirm if line 3 in attachment 3 is required?

Not required

12) Please provide the current pictures of the following items.
    - Granite Tile
    - Pavers
    - Exterior ceiling light fixture

Please refer to the answer to Question 1 and Question 2. Exterior ceiling light fixture is not required.

13) Please provide pictures, color and design or pieces of granite required for exact matching.

Please refer to the answer to Question 1 and Question 2

14) Please provide thickness of Item 2 and 3.

Please refer to the answer to Question 1 and Question 2. Exterior ceiling light fixture is not required.

15) Is there a possibility to purchase the materials in the US and get it delivered to SUVI LLC in New Jersey from there the US Consulate Karachi can import these goods to Pakistan?

All materials and associated goods and services procurement is the responsibility of the vendor/awardee with delivery expected. Furthermore, Samples of all the items needs to pre-approved before the commencement of work

16) Can locally available materials samples be provided for approval?

Yes, but all the items sample should be provided for clearance before the commencement of work

17) Will Consulate logo be provided by Consulate?

Not required