Specifications

BLM BOISE DISTRICT OFFICE
Mobile/Modular Office

The BLM Boise District Office is looking to purchase mobile office space for the purpose of providing office workspace. The site has existing power and will be hooked up by BLM. Ground is a gravel base.

Specifications:

- 40ft (Length) x 8ft (Width) x 9ft 6 in. (Height) (General Measurements)
- Condition: New, not Used.
- Two 36 in. x 80in Man Doors
- Color: Light Beige preferred, but flexible
- Three 36 in. x 36 in. Dual Pane Vinyl Windows w/ Security Bars
- Framed 16 in. OC, R13 Insulation
- Vinyl Wrapped Plywood Interior Finish
- Electrical (In-Wall) 5 Circuits, Four 4ft LED Light
- Electrical Fixtures Minimum: 5 Receptacles, 125 Amp Load Center
- Two Mini Split Heat/AC Units, 2 Zones, 18,000 BTU w/ Thermostat, Remote, Mounting Bracket, and Line Sets

Please note any deviation of the above requirements on your quote. Deviations will be considered and reviewed during evaluation.

Delivery location:

Boise Office Trailer/Modular
12201 South Pleasant Valley Rd,
Kuna, ID 83634

Contact BLM at least 72 hours prior to delivery to ensure staff will be on-site to receive and inspect the unit.

Delivery Contact:
Raul Trevino, Jr
(208) 830-4522
rtrevino@blm.gov