SCHEDULE OF ITEMS

SAULCY WATER WELL
HIGH DESERT DISTRICT

Item No.	Pay Item Number	Description	Estimated Quantity	Unit	Unit Price	Total Amount
1.	WY-02670(1)	Mobilization	1	Lump Sum	$	$
2.	WY-02671(1)	Drilling Pilot Hole (5-inch min dia.)	350	Linear Foot	$	$
3.	WY-02671(2)	Drilling Well Hole (9-1/2-inch min. Dia.)	350	Linear Foot	$	$
4.	WY-02671(3)	Furnish and Install 5-Inch SDR17 PVC Casing	190	Linear Foot	$	$
5.	WY-02671(4)	Furnish and Install 5-Inch SDR17 PVC Slotted Casing	160	Linear Foot	$	$
6.	WY-02671(5)	Gravel Packing/ Bentonite Seal	240	Linear Foot	$	$
7.	WY-02671(6)	Grout/ Surface Grout	110	Linear Foot	$	$
8.	WY-02671(7)	Well Development	4	Hour	$	$
9.	WY-02671(8)	Well Testing	2	Hour	$	$
10.	WY-02672(1)	Final Well Testing	4	Hour	$	$

TOTAL BID (All or none) $