PROJECT DESCRIPTION

FC294 - The work includes Demo existing six existing bay doors. FC294 is an active Fire Department and will be active during the construction of new door installation, one side of bay shall be completed before the other side is started. Contractor shall install a new complete bays door with all new equipment, Curver rails, motors, motor control, sensor, master control, and related hardware and incidental related work.

1606 - The work includes Demo two existing doorway openings. One storefront type and the second is a roll-up door with demo of existing controls, motor, conduit and wiring. Both areas shall have the existing concrete demo and repoured to drawing specifications. Contractor shall install two new double steel doors with removeable mullion, panic bars, hinges, door closers, weather stripping, door sweeps. Door frame shall have side light and transom of still, work to be prime and painted and incidental related work.

G640 - The work includes removing and replacing four (4) refrigerator doors and three (3) freezer door. contractor to provide new doors in existing opening, contractor to repair walls and floor to facilitate the new replacement of door, door frame, door hardware for airtight seal of doors. The contractor shall provide material, equipment and labor as required to accomplish work specified and incidental related work.

WC100 - The contractor shall install a new Remote Condensing Unit on the roof of WC100 to bring freezer Box (A) back into operation

SPECIAL SCHEDULING

The facility/activity will remain in operation during the entire construction period. The Contractor shall conduct his operations so as to cause the least possible interference with normal operations of the facility/activity.

SUPERVISION

One person may fill the roles of Superintendent, Quality Control Manager, and Safety & Health Officer, if duly qualified for all three positions as defined in the project specification.