STATEMENTOF WORK
FOR

71 SFS Armory Weapons Racks
Vance AFB, OK

2 Jul 2026

PART 1 GENERAL

1.01. LOCATION

A. Location of the work to be accomplished under this statement of work is at Vance Force Air Base. Vance Air Force Base is located south of the city of Enid, Oklahoma just off U.S. Highway 81 and Southgate road. Work will be performed at the Security Forces Armory Bldg 527.

B. Points of Contact:

Facility Manager: SSgt Robert Scholz, 580-213-7147

Alt Facility Manager: SSgt Noah Myers, 580-213-7147

1.02. SCOPE OF WORK

The work covered under this statement of work shall consist of furnishing all materials, labor, and equipment in performing the installation of Universal Weapons Racks IAW attached quote and mechanical drawings dated 6/5/2026.

1.03. SCHEDULE OF WORK

A. The contractor will mount the racks, other storage cabinets and shelving as described in quote and attached mechanical drawing dated 6/5/2026.

1. Provide 7-UWR4 M-4 Rifle & M18 Pistol storage racks, 2-UWR1 Rifle storage components, 1-UWR2 component, 1-UWR3 component, 1-UWR5 component, 2-UWR6 components and 1 - Mobile Storage Bench w/ Cabinet.

2. Perform test and inspection to ensure all racks and shelves are properly secured to floors and/or walls and all locking systems operate as designed. The contractor must ensure area is cleaned of debris and and tools. An inspection will be conducted by the facility manager with the contractor, prior to accepting the completed project.

B. Hazardous Materials Safety Data Sheets must be provided for any hazardous that is used. The contractor must obtain the proper documents from the 71 SFS to ensure all materials leaving Vance Air Force Base can be tracked and accounted for, in accordance with all governing laws. Ensure the review of all MSDSs associated with the adhesives and chemicals used proper PPE and

ventilation recommendations.

1.04. CONTRACTOR'S REPRESENTATIVE

A. A Unit representative shall directly supervise accomplishment of this work. This representative shall be responsible for coordinating all phases of work with the facility manager. The representative shall be on the job site or readily accessible at all times work is being performed and shall have authority to execute no cost field changes on behalf of the Contractor if agreed to by all parties involved.

B. This person will also be responsible for all Quality control of the job site and will be held responsible by the Contracting Office for the removal and installation of all work in accordance with this statement of work. The representative shall be competent and familiar with all phases of work under his authority. The Contractor's representative shall have in his possession a minimum of one cell phone; this telephone number will be on record with the Facility Manager.

1.05. PROVIDED SERVICES AND UTILITIES

There are water hydrants and electrical outlets in close proximity of this work site.

1.06. INSPECTION

The work will be conducted under the general direction of the Facility Manager and is subject to the inspections of the appointed inspectors(s) to ensure strict compliance with the terms of the contract.

1.07. EXCESS MATERIALS (EXCLUDING HAZARDOUS MATERIALS OR WASTE)

All materials resulting from accomplishment of this work will be disposed of in a container provided by the range and disposal is the responsibility of Armory Officials.

1.08. SPECIAL MATERIALS

A. Prohibited Material: The manufacturer of materials that are to be used in this contract has certified that the product does not contain mercury, toluene, chlorinated solvents, hydrolysable chlorine derivatives, ethylene based glycol ethers and their acetates, nor any carcinogen, as defined in 29 CFR 1910.1200. Materials used shall not contain lead and hexavalent chromium compounds. In addition, the Contractor shall comply with Federal regulation 16 CFR-1303 in the use of lead, use on touch-up for damaged furniture or any interior surface of a facility. If lead based paint is used it shall be tested as specified ASTM-D 3335, the lead content shall not exceed 0.006 percent by weight of the dry film and the test for chromium content shall be negative.

B. At no time shall class 1 Ozone Depleting Chemical (ODC's) be specified and shall not be used.

PART 2 EXECUTION

2.01. INSTALLATION

A. All work may be performed 0800-1700, Monday through Friday.

B. The contractor working with Armory Officials, will at all times have a working schedule as to the times his installers will be working.

C. The Contractor will be liable for any and all replacement costs of equipment items or property damaged by installation.

THIS SHEET LEFT BLANK INTENTIONALLY