Solicitation #: 140P6426Q0114

Amendment #: P0001

FILA – Water Meter Replacement

Questions and Answers listed below:

QUESTIONS:

Question #	Question	Answer/Response
1.	May we, as the prime contractor, use a licensed commercial plumbing subcontractor to perform the specialized on-site plumbing work?	Yes
2.	May we rely on the subcontractor's licenses, qualifications, technical experience, and project references to meet the solicitation requirements?	Yes
3.	Please confirm whether subcontractor project references will be accepted for the required three similar projects completed within the past five years.	Yes
4.	Please confirm the exact size and material of the existing main water line, bypass piping, valves, tees, and flanged connections.	4" on main and 3" bypass
5.	The Statement of Work refers to a 3-inch bypass loop connected to a 4-inch main line. Please confirm that these dimensions are correct.	Yes
6.	Please provide the exact model number, specifications, flange requirements, and installation drawing for the Government-furnished Sensus Cordonel-P ultrasonic meter.	Cordonel -P 4" Mod. 101715794
7.	Please confirm whether the Government-furnished meter has a 20-inch lay length.	20"
8.	Will the City of Canton perform the main water shutdown, meter sealing, and final inspection, or must the contractor arrange these services?	The city will have to turn off the water at the curb to replace meter and valves. There is not a shutoff valve before meter.
9.	Are permit fees, inspection fees, water-department fees, or shutdown charges the contractor's responsibility?	These fees are N/A. This is a Federal Facility.
10.	Is a pre-quote site visit available so interested contractors may verify measurements, access conditions, piping layout, and existing corrosion?	There is no scheduled site visit. However, contractors can inquire with the CO and something can be set up.
11.	Please confirm whether the fire alarm, fire suppression, emergency impairment, and fire-system inspection language in the Statement of Work applies to this water meter replacement project.	The meter replacement is separate from the fire main.
12.	Please confirm whether the contractor is responsible for replacing any pipe insulation removed or damaged during the work.	Yes

13.	Please confirm whether the contractor must provide temporary water service or temporary fire-protection service during the shutdown.	No
14.	Please confirm whether all physical removal, installation, testing, and restoration work must be completed within the three-day Monday-through-Wednesday shutdown window.	Yes
15.	Please confirm whether any specific City of Canton plumbing registration, permit, backflow certification, or water-department credential must be submitted with the quotation.	The city will have to turn off the water at the curb to replace meter and valves. There is not a shutoff valve before meter.