140L5726Q0027

Q&A's

Q1. Could you please confirm that the quantities should be as follows: Cattle Guard Bases (20 sets of 2), Cattle Guard Wings (20 sets of 2), and 8' Cattle Guard HS20 (20 each)?

A1. The numbers are correct as these will be for ten 16' cattle guard openings.
20 each wings (10 sets of 2)
20 each cattle guards
40 each bases (20 sets of 2)

Q2. Is the Cattleguard fabrication weldment option <u>with</u> or <u>without</u> the CLEANOUT?

A2. The cattleguard weldment/grate does not need a cleanout.

Q3. Is the Swing Wing considered part of the End Wing assembly, or is it a separate scope of work that should not be quoted with the required End Wing?

A3. A swing wing will not be part of this contract. Just the tubular or angle iron end wings need to be included.

Q4. Regarding pre-cast pieces:
-required beam length - confirming 8' each please
-specified concrete strength?
-rebar finish - uncoated or epoxy-coated?

A4. For the question regarding the concrete bases:

- Beam length for the concrete bases is 8 feet. That is listed in the specification document as well.
- Concrete strength must be 4,000 PSI minimum.
- Uncoated rebar is sufficient.