

1. **Equipment Rack:** Is there an existing equipment rack or rack-mount cabinet at the central TV distribution/headend location in each of the three buildings? If so, can you provide the rack size/RU capacity and approximate available space?
 - Currently IT has a 2 post rack for all the NDC Central Buildings Patch Panel, Fiber, Switches and UPS's. There is approx 6U available on these racks. The current System has 2 portable racks on wheels, used for the TV boxes for each room. The cables and all other splitters, etc are mounted on the wall, which will be available for the vendor mount their own racking if needed. (see pics)
2. **Internet Service:** What internet service and bandwidth are currently available at each of the three buildings and at the chapel/live-stream locations? If available, could you provide the approximate upload and download speeds and whether Ethernet connectivity is available at the headend locations?
 - The County uses a 10GB connection to CINC for it's internet. All buildings and closets are connected via fiber and when using ethernet average speed is 900 mbps + Up/Down. Ethernet is available at the headend locations, but usage will need to be discussed because the current system is not utilizing it. The chapels do have Ethernet ports available. There is WiFi throughout all buildings.
3. **Building Floors:** How many floors/stories are in each of the three buildings included in the project?
 - There is only one floor in each of the 3 buildings
4. **Demarcation/Headend Locations:** Could you identify what equipment and services are currently present at the TV system demarcation or central distribution/headend point in each building, including any existing amplifiers, modulators, encoders, distribution equipment, or network connections?
 - We are unsure of what equipment and exactly how it all flows through out to the Residents rooms. The system was installed when the building was built and the project managers at that time are no longer at the County. See attached pics for a visual on the equipment at the Central Headend area and 1 of the 3 central closets. (They are all hooked up the same way)